

# Lyb-43

Workover Rig 375 HP IDECO SBS DIR-5506/A

### **DEPTH RANGE:**

2500 m with 2 7/8" DP, 3800 m with 3 1/2" Tubing

#### SUBSTRUCTURE:

Height: 4.6 m (15.09 ft) Height under rotary beams: 3,8 m (12.07 ft) Set Back: 80 mt

#### MAST:

IDECO-SBS KM-111-268 GH, 33.8 m (110.9 ft) Capacity: 121,6 mt

## **CROWN BLOCK:**

No of sheaves: 5 Grooved: 1" Capacity: 121,6 mt

## **TRAVELLING BLOCK & HOOK:**

YG-150 Capacity: 136 mt

#### SWIVEL:

IDECO TL-200 Capacity: 181 mt

## **DRAWWORKS**:

H 37 ED IDECO 1" Capacity: 375 HP

#### **ROTARY TABLE:**

LR-175, 17 1/2" Capacity: 147 mt

### **RIG POWER SUPPLY:**

Diesel Engines: 1 x CAT 3406 DITA Capacity: 380 HP

#### **MUD PUMPS:**

1 x RGF-500 powered by 3412 CAT Capacity: 650 HP



## **MUD TANKS:**

Mud Tanks: Brine mixing tank 3 x 30 m3 Water tanks: 1 x 43 m3